

NSLS-II Booster



Sergei Gurov for the BINP and NSLS-II team

Budker Institute of Nuclear Physics

Presentation at SFR-2016

Novosibirsk


4 July 2016

Brookhaven National Laboratory

National Synchrotron Light Source

and

National Synchrotron Light Source II



NSLS (1982 – 2014)

Brookhaven Laboratory located in the center of Long Island, in 100 km from New York.
In the first three decades of operation , the NSLS has yielded many discoveries and two Nobel Prizes.
The new NSLS-II will produce x-rays more than 10,000 times brighter than the original NSLS.

NSLS-II main parameters

Energy	3 GeV
Ring circumference	792 m
Horizontal emittance	$<1 \pi$ nm rad
Vertical emittance	8π pm rad
Beam current	500 mA
Number of RF buckets	1320
Number of bunches	1056
Average bunch charge	1,25 nC
RF frequency	500 MHz
RMS energy spread	0,1%



BNL announced a tender on the booster synchrotron which shall be capable of accelerating electron bunches from the minimum linac energy of 170 MeV to a maximum extraction energy of 3,15 GeV for injection into the main storage ring.



The proposal from BINP on the turn-key booster were the most attractive and the contract was signed in May 2010.

BNL and BINP cooperation



BINP produced 21 quadrupole magnets of the 30Q44 and 30Q58 types for the SNS, designed by BNL

BINP produced 128 quadrupole magnets of 6 types for the NSLS-II Main Ring



BINP produced three helical undulators for proof-of-principle experiment on coherent electron cooling.

Table 4.1. General Booster Specifications

Circumference	158.4 m	68%
Super-Periodicity	4	
Operating time per year	6000 hr	
Unscheduled Downtime	0.4% (24 hr per year)	
Repetition rate	1 Hz (2 Hz)	
RF frequency	499.68 MHz $\pm$ 10kHz	
RF voltage	200V - 1.2 MV	
RF Amplitude and phase jitter at 1.2 MV	$\pm 1\%$ and $\pm 1^\circ$	
Max RF power	72 kW	

Table 4.3: Parameters of the Electron Beam Extracted from the NSLS-II Booster

Nominal extraction energy	3 GeV
Horizontal Emittance	<40 nm rad at 3 GeV
Momentum Spread	<0.1%
Extracted Beam Angle Jitter	<20% of beam divergence
Coupling	<10% at 3 GeV
Charge (Long pulse/ Single pulse mode)	>10 nC/0.5 nC
Charge transport efficiency between ICTs in LB and BSR TL	>75% (achieved up to 98%)

Scope of work




- Beam dynamics cross checking
- Design and production of booster ring (158 meters)


Including:

- Magnets (28+32 dipoles, 24 quadrupoles, 16 sextupoles, and 36 correctors)
- 160 meters of vacuum channels
- Injection and extraction (bumps, kickers, pulsed and DC septums)
- Power supplies
- Diagnostics
- Control System and software (together with BNL)
- Infrastructure (cables, water, and air) (together with BNL)

Excluding: RF system (PETRA 7-cell 500MHz Cu-cavity)


- Installation (together with BNL)
- Testing (together with BNL)
- Commissioning (together with BNL)
- 2 year warranty





Tender
 Contract signing
 Preliminary Design Review
 Final Design Review
 Production Readiness Review
 Booster Delivery
 Assembling
 Testing
 Extending Integrated Testing
 Commissioning

February – March 2010
 07.05.2010
 October 2010
 February 2011
 July 2011
 December 2011 – June 2012
 February – November 2012
 May 2012 – January 2013
 February – October 2013
 09.12.2013 – February 2014



Contract has been signed on 7 May 2010





After 14 months booster was designed

and all first article is ready: BD and BF dipoles,
quadropole, sextupole,
CX and CY correctors,
girder, 6A power supplies.




After 28 months in August 2012 all booster components have been delivered to BNL (New-York)

Magnets


BF dipoles, 28 BD dipoles, 32	S. Sinyatkin A. Sukhanov
Quadrupoles, 24	A. Philipchenko V. Kobets
Sextupoles, 16	A. Utkin N. Nefedov
CX Correctors, 20 CY Correctors, 16	V. Petrov V. Konstantinov
Girders, 44	A. Polyanskiy L. Shegolev




Magnetic measurements



Extraction



Injection



Main technical parameters of the injection magnets

	Leff [mm]	h gap [mm]	Fi [mrad]	H [T]	I [A]	U [V]	T/4 [μcek] (Flat-top)	Stability dH/H [%]
IS-KIC3	20.5	38	15	0.0488	1 477	20 500	(0.3)	± 0.5
IS-KIC4	20.5	38	15	0.0488	1 477	20 500	(0.3)	± 0.5
IS-SMP1	750	30	125	0.1112	2 660	195	52	± 0.1

Main technical parameters of the extraction magnets

	Leff [mm]	h [mm]	Fi [mrad]	H [T]	I [A]	U [V]	T/4 [μcek] (Flat-top)	Stability dH/H [%]
XS-BUMPS	16.9	33	7.9	0.465	1 530	846	728	± 0.02
XS-KIS1	2*20.5	38	0.283	0.069	2 088	22 000	0.3	± 0.2
XS-KIS2	2*20.5	38	0.283	0.069	2 088	22 000	0.3	± 0.2
XS-SMP1	600	16	48	0.8	10 200	470	78	± 0.02
XS-SMD1	1252	20	106	0.847	322	10	----	± 0.02

Power supplies of injection and extraction kicker, septum and bump magnets



Extraction Straight



Equipment Protection System



Power supplies for ramped magnets



Power supplies for DC septum
and quadrupole magnets




MPS6 – 8 channel crate
for corrector and
sextupole magnets



Power supplies for dipole magnets
from our subcontractor Danfysik




Booster Control System





Diagnostics


- 36 BPMs
- The tune measurement system
- 6 Fluorescent screens
- 2 SR monitors
- DCCT and FCT




Six fluorescent screens




ISVF2 – fluorescent screen after injection.
Central bar is 6 mm x 9 mm




Beam Current along Ramping



Beam Current along Ramping





36 BPMs




XS-PKU1

Показания без учета нелинейности
и оффсета -6,1мм

Равновесное положение
пучка -10,5 мм





☐ 2	☐ 12
☐ 3	☐ 13
☐ 4	☐ 14
☐ 5	☐ 15
☐ 6	☐ 16
☐ 7	☒ 17
☒ 8	☒ 18
☒ 9	☒ 19
☒ 10	☒ 20




☐ 1	☐ 11
☐ 2	☐ 12
☐ 3	☐ 13
☐ 4	☐ 14
☐ 5	☐ 15
☐ 6	☐ 16
☐ 7	☒ 17
☒ 8	☒ 18
☒ 9	☒ 19
☒ 10	☒ 20


Beam orbit after correction



Ramp manager and degauss of magnets



Ramp Manager





The tune measurement system



○ STOP
● RUN_PULSE


Tune



idx	sec	v_x	v_y
10	0.011	0.622371	0.642999
100	0.108	0.626001	0.626578
250	0.271	0.510647	0.657236



☒ v_x ☒ v_y ☐ Ampl ☐ v_x ☐ Ampl ☐ v_y ☒ Energy ☒ Win v_x ☒ Win v_y ☒ Marks

The tune measurement system



☐ STOP
☒ RUN_PULSE

Tune Mea



idx	sec	v_x	v_y
10	0.011	0.582493	0.614119
100	0.108	0.577524	0.620371
250	0.271	0.57649	0.621337

☒ v_x ☒ v_y ☐ Ampl v_x ☐ Ampl v_y ☒ Energy ☒ Win v_x ☒ Win v_y ☒ Marks

Booster Status Monitor

Currents and Efficiency

Overall

93.28 %

Monitoring mode

Ref

Extra

Save/Restore Info

11 Feb 2014 23:26:06

ssinyatkin

(T)

RampManager file

ramp_3GeV_2mA

Graph Config

Currents and Efficiency

Overall

93.28 %

LTB Out
3.04 mA

Booster In
3.08 mA

Booster Out
2.93 mA

BTS In
2.74 mA


Injection
99.18 %

Acceleration
93.45 %

Extraction
100 %

1nC = 1,9mA

Energy and Current






Energy


Booster In
201.21 MeV

Booster Out
2983.18 MeV

Two SR monitors



Emittance Measurement




E = 3 GeV :

$Em_x = 40 \text{ nm*rad}$ => Later 35 nm*rad

$Em_y = 3.7 \text{ nm*rad}$

“The injector complex is very robust. After a break or shutdown, full performance is reestablished after only a few hours. Operation is fairly reliable and re-tuning is required only rarely”, Ferdinand Willeke, IPAC2015, “COMMISSIONING OF NSLS-II”.





Work under kicker modulators



Thank you!



The way from control room towards NSLS-II during commissioning



Extraction Straight