




The MAX IV Accelerator Facility, concept, status and perspectives

Mikael Eriksson on behalf of the MAX IV team

SRF 2016

Diffraction Limited Storage Rings


$$\frac{\lambda}{4\pi}$$

Receipt for designing a very low emittance ring:

$$\textit{Brilliance} \propto \frac{1}{\varepsilon^2} \quad \varepsilon = C_q \frac{\textit{Energy}^2}{(N_{\textit{magnets}})^3}$$

Increasing the number of cells is a powerful way to increase brilliance.


But:

- The ring will get a 2 km or so circumference.
- The Dynamic Aperture is reduced


So:

- We make the components small to squeeze in a large number of magnets
- We design stable Multi-Bend Achromats (MBA)

3rd Generation




MBA




courtesy of C. Steier

MAX IV - An integrated Solution



DLSRs: why not earlier? - lattices



Multibend achromat (MBA) lattices

- Lattice design evolution from DBA, TBA to 4BA,...MBA:

- History (partial):


1993: QDA by D. Einfeld et al. NIMA 335(3)

1994: SLS early design with 7BA, short superbend, provision for on-axis injection (W. Joho, P. Marchand, L. Rivkin, A. Streun, EPAC'1994)


1995: 7BA by Einfeld et al. (0.5 nm-rad, 3 GeV, 400m, PAC 95)

2002: MAX-IV 7BA concept (M. Eriksson, Å. Andersson, S. Biedron, M. Demirkan, G. Leblanc, L. Lindgren, L. Malmgren, H. Tarawneh, E. Wallén, S. Werin, EPAC 2002)

MAX IV – an overview




© Photo: Perry Nordeng
18-Sept-2014




| | | |
|---------------------|------------|--------|
| Energy | 3 | GeV |
| Current | 500 | mA |
| Emittance | 0.2 - 0.33 | nm rad |
| Circumference | 528 | m |
| # straight sections | 20 × 5 m | |

Civil Engineering





www.ekdahlgeo.se

Beam parameters Thermionic Gun



Slide by S.Thorin






The MAX IV 3 GeV ring Lattice

7-bend achromat

20 periods


| | |
|---|------------------------|
| Periodicity | 20 |
| Circumference | 528 m |
| Horizontal tune ν_x | 42.20 |
| Vertical tune ν_y | 16.28 |
| Natural horizontal chromaticity ξ_x | -49.984 |
| Natural vertical chromaticity ξ_y | -50.198 |
| Momentum compaction (linear) α_c | 3.06×10^{-4} |
| Horizontal damping partition J_x | 1.8471 |
| Bare lattice emittance ε_0 | 0.328 nm rad |
| Bare lattice energy loss per turn | 363.8 keV |
| Bare lattice natural energy spread σ_δ | 0.769×10^{-3} |
| Bare lattice horizontal damping time τ_x | 15.725 ms |
| Bare lattice vertical damping time τ_y | 29.047 ms |
| Bare lattice longitudinal damping time τ_E | 25.194 ms |
| Horizontal beta function at center of LS β_x^* (bare lattice) | 9.00 m |
| Vertical beta function at center of LS β_y^* (bare lattice) | 2.00 m |

One of 7 integrated magnet blocks in a MAX IV achromat.
The ring contains 20 achromats.




MAX IV 3 GeV Ring DC Magnets


- *Each cell is realized as one mechanical unit containing all magnet elements.*
- *Each unit consists of a bottom and a top yoke half, machined out of one solid iron block, 2.3-3.4 m long.*
- a U5 bottom half →
- ↓ an assembled U5




Cu, NEG-coated MAX IV Vacuum chamber




- BPM Bodies fixed to the Blocks.
- Geometry is as symmetrical as possible – if heat load changes , dimensions change but center (nearly) does not move.






100 MHz Capacity-loaded Cavity for MAX-II and -III, $F = 100.08317$ MHz






March 2016

3 GeV Ring Commissioning Timeline





Early Commissioning Results



- Beam observed at the end of TR3 and into the ring.

2015/08/11


Threading the beam – first turn – many turns




2015/08/25

3 passes

All correctors OFF




2015/08/26




35 passes

2015/08/27



First Stored Beam



Injected beam






Stored beam 2 seconds after previous injection pulse

Injection

Kicker Current

2015/09/15

Capture and Bunching





Plots S. Leeman

March 2016

DLSR Workshop 2016


2015/09/23

Linear Optics Characterization: Integer Tunes




LOCO: reduction in dispersion beating


Before LOCO



After LOCO



Chromaticities:




01-Feb-2016 22:28:33

BPM Offsets



- Measured by BBC using trim coils in sextupole magnets

RMS: 144 μm H / 138 μm V





Orbit Correction

Residual RMS: $0.7 \mu\text{m}$ H / $62 \mu\text{m}$ V



Bare Vertical Orbit


Plot by M.Sjöström




Example calculation for one random seed

MAX-lab Internal Note 201211071 by
S.Leemann




Injection Efficiency - 2




Vacuum Conditioning - pressure




Beam Lifetime



Aperture Scans – scraper measurements



Plot by Jens Sundberg






2011 simulations by S.Leemann

Vertical aperture scaled to center of LS 2.3 mm

Collective Effects – Single Bunch

- No signs of TMCI up to 8.55 mA (nominal 2.8 mA/bunch).
- Significant bunch lengthening even without harmonic cavities





Data by J.Breunlin,
A.Andersson, G.Skripka,
R.Nagaoka

Collective Effects - Multibunch

- Possible to store >120 mA without feedback and without harmonic cavities. Predicted RW threshold was only ~ 40 mA !
- HOM driven longitudinal motion is evident at a few mA in uniform fill.
- Temperature tuning has proved effective in fighting longitudinal CBI.
- Harmonic Cavities not fully tuned-in in yet. Need more conditioning
- Preliminary BBB feedback tests using a short stripline showed a longitudinally stable beam up to 35 mA.
- Longer striplines for BBB feedback to be installed in february
- Longitudinal Actuator (cavity) under design

Emittance Measurement



Sigma polarized SR, 632.8 nm, SRW calculation (left) and measured image (right). The simulation is done for $\epsilon_x = 320$ pm rad, $\beta_y = 1.5$ m.

Both figures show a 2×2 mm² area of the image plane.



The fringe pattern is too weak to be visible.

Optical magnification of $m = -2.28$ is taken into account in the SRW model

Horizontal opening angle: 6 mrad

Vertical opening angle: 8 mrad

Exposure time: 2.9 ms



Horizontal intensity profile of imaged sigma polarized SR. Due to the reduced horizontal opening angle the fringe pattern is not as pronounced as it could be, but easier to understand and to calculate.

Present setup is limited by optical aberrations (from misalignments) and surface quality from optical components (some are inherited from MAX II, MAX III). Steady improvements during the next weeks are planned. Camera linearity might also be an issue!

Challenges on the SRW model side are to include for example: variation of dipole field, variation of β_x , variation of vertical opening angle, along the observed electron beam path.

Main Problems/Difficulties

- RF Cavity Conditioning
- RF System commissioning (LLRF, Shunt Groups)
- Diagnostic System Commissioning
 - BPMs
- Kicker Magnet PS failure
- Gun Klystron Failures
- Long Radiation Surveys
- Cooling System Failures
- Control System Commissioning
- PS Failures

Help from friends:

BINP: Vacuum system installations

ESRF: Complicated NEG coating

MAC: Most valuable advices

Solaris: Operations


DESY: RF components

And many more...

Conclusions

- Progress with the initial phase of MAX IV 3 GeV ring commissioning gives us increased confidence that the MBA concept is sound.
- Much is still to be done to reach the final design specifications, but nothing indicates there is any fundamental obstacle ahead.
- Most difficulties are related to technical subsystems that need time for conditioning/maturing

MAX IV: Forerunner of a new breed of accelerators



Thank You !

