

Plan for DESY VXD Integration Test


Katsuro Nakamura

Sep. 6, 2016


TRG/DAQ Workshop


VXD Beam Test Campaign

- Combined beam test (= BT) of VXD = PXD + SVD
 - Geometrical setup is same as phase-2
- e- beam with momentum of 2-5 GeV/c
- Full readout DAQ chain
- 1T B-field in PCMAG
- Nominal trigger rate: ~500Hz



PXD Test Beam Set Up







SVD setup in DESY BT campaign (1)

Same setup as phase-2

- One SVD ladder in each layer
- Total 4 SVD ladders




SVD setup in DESY BT campaign (2)





DAQ setup in DESY BT campaign



History of DESY VXD BT campaign


- Jan. 2014: 1st DESY BT campaign
 - PXD: sensor in pilot production
 - SVD: prototype DSSD module
 - Conceptual confirmation of VXD-DAQ was achieved.
- Apr. 2016: 2nd DESY BT campaign
 - PXD: Final DEPFET sensors with prototype ASICs. Only BWD sensors were installed.
 - SVD: Final ladders (but class-B = lower grade)
 - We encountered several issues on VXD-DAQ. We decided to have another campaign to tackle them.
- Dec. 2016 (+ Jan. 2017?): 3rd DESY BT campaign
 - PXD: Final sensors with final ASICs
 - SVD: Final ladders (but class-B)
 - + BEAST sensors
 - compatible setup as phase-2 VXD

We deeply appreciate large contributions of DAQ group for great successes in the previous BT campaigns!

Hit maps for selected events

SVD hit maps (ϕ -direction = p-side)


from T. Luck slides, Jun 21 B2GM




Hit maps for selected events


SVD hit maps (z-direction = n-side)

from T. Luck slides, Jun 21 B2GM



SVD hit/cluster inefficiency (1 - efficiency)






- very high efficiency, > 99%
- some inefficiencies by known defects, new defects and selection

PXD Hit Maps

PXD Hit Maps


Threshold = $5 (\sim 1200 \text{ electrons})$



Trigger on 4 scintillators Collimated beam No magnetic field

Both detectors fully functional

PXD Residual Distributions





Residuals for perpendicular incident MIPS:

- 14 μm (50 μm pitch)
- 18 μm (60 μm pitch)

Cluster size ~1 – binary resolution

PXD ROI efficiency





from Spruck-san's slides

https://indico.mpp.mpg.de/event/4412/contribution/0/material/slides/0.pdf

- Offline ROI: Distance cut (<1mm) around extrapolated intersection
- Data sample: run329 (all subruns)
 - ~2h long run
 - 5GeV e- beam in 1T field
- PXDTriggerShifter not active (Module removed from path)
- Quality cuts on SVD tracks:
 - Only single track events
 - p-value > 0.01
 - p>3GeV && p<8GeV</p>

(plots from Benjamin)

Issues on 2nd VXD BT Campaign

~ PXD ~

- Only half ladder (only BWD) was tested.
 - Full ladder will be prepared by the next BT campaign.
- Some Links between DHP-DHE were unstable
 - Optical links for final experiment will improve the stability.
- Event number mismatch between DHEs
 - Above broken links caused an "extra" event in DHE which caused this event number mismatch.
- DHP or matrix coordinate mapping (DHE-ONSEN)
 - Fixed, clustering in the DHC
- Large trigger veto (100usec or 300usec) was applied for PXD-DAQ
 - Under investigation. This must be reduced into ~600nsec.

Issues on 2nd VXD BT Campaign

~ SVD ~

- Short study time for attack to the SVD noise issue
 - Most likely, the biggest noise source seems a water chiller beside PCMAG.
 - We have to study how this affects our data qualities.
- An issue on trigger veto in SVD FADC system for the triggertiming scan run.
 - FPGA firmware issue. Can be fixed easily and soon.
- SVD internal event number mismatch
 - Due to an issue in process of trigger number decoding from FTSW signals (in FADC-Ctrl)
 - APV-emulator firmware is necessary to check correctness of event order. This will be developed and tested at the next BT campaign.
- Data format in FTB-DATCON
 - must be revised by the next BT campaign.
- Further development is necessary for SVD slow control
 - will be improved by the next BT campaign.

Issues on 2nd VXD BT Campaign

~ VXD ~

Event number shift between PXD data and SVD data on ONSEN

- Most likely, due to an issue in process of trigger number decoding from FTSW signals (in DHC).
- This is to be confirmed.

ROI feature of DATCON-ONSEN is not working properly yet

- Further development seems necessary.
- Need to be solved in the next BT campaign

Data taking with high rate triggers

So far, we haven't confirm the feasibility for such high rate DAQ.

Acceptance of sensors

 Hit efficiencies on sensors are measured. We should also check the acceptance of fiducial regions in sensors.

Plan for 3rd DESY BT campaign

Requirement:

- VXD DAQ must be well debugged before the BT campaign with well coordinated schedule.
 - Event-mixing problem must be completely solved.
 - FTB-DATCON-ONSEN line must be established.
- Integration test for BEAST sensors in VXD volume (FANGS, CLAWS, and PLUME)
 - check proximities between detectors and grounding interference.

Proposal:

- Permanent VXD DAQ setup at DESY
 - even after the next BT campaign
- Improve BonnDAQ so that it can send dummy PXD hit information to ONSEN.
- Step-by-step increasing complexity with each data link check
- Dry integration of BEAST sensors on PXD and SVD
- Final BT in Dec. 5 Dec. 23



DESY Testbeam Schedule 2016 - Version 8 - 27/04/2016

cnec	V el 🗀	Marcel Stanitzki - DESY Test Bean TB21	TI	322	TB2	4/1	TB24
			ne DURANTA	none	Telescope in PCMAG	PCMAG	none
4-Jan-16	1						
11-Jan-16	2	_					
18-Jan-16	3						
25-Jan-16	4		CI				
1-Feb-16	5	_	21	าutdoง	wn		
8-Feb-16	6	_					
15-Feb-16	7	_					
22-Feb-16	9	_					
29-Feb-16 7-Mar-16	10	Charles	610	****	Co.	A com-	Charles
		Startup CMS-Pixel-Phase1		irtup	Star	tup	Startup
14-Mar-16 21-Mar-16	11	Goettingen-CMOS	Mu3e ATLAS-Pixel-AMSH35				+
28-Mar-16		ATLAS-Pixel-MPP	ATLAS-FIXET-AIVISHSS				+
4-Apr-16	13 14	CMS-Pixel-Phase1					
11-Apr-16	15	PLUME					
18-Apr-16	16	PLUME		\vdash		Belle-II	
18-Apr-16 25-Apr-16	17	CMS-Pixel-Phase1					
	18	CIVIS-PIXEI-PHASE1		CALLCE ALLCAL			Cinna
2-May-16 9-May-16	19	ATLAS-DMicromegas		CALICE-AHCAL CALICE-AHCAL			SiPM SiPM
16-May-16	20	ATDAS-DIVITA OTHEGAS		CALICE-ARCAL			SIPIVI
23-May-16	21	ATLAS Strin Clus	ATLAS-ITK-Strip		A 6		_
30-May-16	22	ATLAS-Strip-Glue ATLAS-Strip-Glue	ATLAS-ITK-Strip				+
	23	CMS-Phase2-EPI	ATLAS-ITK-Strip		4	<u> </u>	CMS-Pixel-Pha
6-Jun-16 13-Jun-16	24	CMS-Phase2-EPI					CIVIS-PIXEI-Pha
20-Jun-16	25	CWS-Phase2-EPI		CALLCE ALICAL		2	_
27-Jun-16	26			CALICE-AHCAL			_
4-Jul-16		CMS Divel DIL KA			3 0		
4-Jul-16 11-Jul-16	27	CMS-Pixel-PII-KA CMS-Pixel-PII-KA					+
11-Jul-16	28	CIVIS-PIXEI-PII-KA		 			+
25-Jul-16	30		ATLAS-Strip-Glue				+
1-Aug-16	31	Summer Students	ATLAS-Strip-Glue				+
8-Aug-16	32	Juliller Judents	ATEAS-Strip-Gitte				
15-Aug-16	33						
22-Aug-16	34	FCAL					
29-Aug-16	35	1 CAL					CBM-TRD
5-Sep-16	36						CDIVI-TRD
12-Sep-16	37	1					
19-Sep-16	38						
26-Sep-16	39						
3-Oct-16	40				1/1/	50 B	Contractor
10-Oct-16	41				VX	D Dry T	ests
17-Oct-16	42	CMS-Phase2-EPI					
24-Oct-16	43	CMS-Phase2-EPI	HEP for Teachers				
31-Oct-16	44						
7-Nov-16	45	1	Mu3e				
14-Nov-16	46				TOTAL DE	The second	Control Control
21-Nov-16	47				Phase 2	Dry In	tegratio
28-Nov-16	48			4	r llase 2	PI Y IIII	tegratic
5-Dec-16	49			200			
12-Dec-16	50					Belle-II	
19-Dec-16	51 Beam till 23						


Preparation schedule of 3rd DESY BT campaign (still not clear yet)


- We should have core weeks in which all the experts can work together.
 - We need to determine when and how long.
- Before the BT, Two or three DAQ members will come to DESY in early Nov. for about a week.
 - This must be before B2TIP meeting at MIAPP (Munich) Nov. 15-17
 - They will rebuild PocketDAQ setup and perform dry runs with VXD modules.
- Before the start of BT, we must confirm whole chains of VXD-DAQ work properly.
- From Dec. 5: 3rd DESY BT campaign
- We have to clarify:
 - Travel funding from Japan to Europe
 - Detailed schedule of core weeks and preparation
- These scheduling issues will be dedicatedly discussed on the coming VXD workshop (Sep. 14-16). After the workshop, the detailed preparation schedule must be clear and circulated to all relevant members immediately.

backup


Measured momentum distribution in SVD

from T. Luck slides, Jun 21 B2GM








Nombre		10 oct 16	17 c	oct 16	24 oct 16		31 oct 16		7 nov 16		14 nov 16		21 nov 16	<i>a a a</i>	28 nov 16
Nottible	JVSD	L M M J V	SDLN	MMJVSD	LMMJV	SD	L M M J	V S D	LMMJVS	D	L M M J V	SD	L M M J	V S D	LMMJV
Network															
Power Supplies															
PXD Data Acquisition															
PXD					-	V									
Dry box final sensors															
BEAST										Į.	,				





Nombre		10 oct 16	17 oct 16		24 oct 16		31 oct 16		7 nov 16	14 nov 16	21 nov 16	28 nov 16
Nottible	JVSD	L M M J V	SDLMM	JVSD	L M M J	V S D	L M M J	V S D	LMMJVS	D L M M J V S	D L M M J	V S D L M M J V
Network												
Power Supplies												
PXD Data Acquisition												
PXD						•						
Dry box final sensors									-			
BEAST			,1	.1 **								














In the latest schedule, cabling work on KEK is moved to Dec.

cmarinas@uni-bonn.de

TRG/DAQ workshop 2016

