



DAQ : General Status

R.Itoh, KEK

Belle II DAQ System



Belle II Schedule



- The operation of SuperKEKB accelerator had been started from the beginning of this year although the beams are not yet collided.
- “BEAST” detector was implemented in the IP to monitor the background level


June 18, 2016 (LER beam current at 970 mA, HER at 870 mA)





Activities of data-taking towards Global CRT


- Backend DAQ is flexible for standalone or combined cosmic data tests.
 - FTSW : one combined CRT + standalone CRTs.
- (Except for CDC. It can be combined with another sub-detector like CDC+TOP)

-> As for backend DAQ and TTD(not trigger source), combined CRT by global DAQ system is possible.

**Global Belle II DAQ(COPPER to storage)**

Pocket DAQ in E-hut

PocketDAQ of each det. Gr.



DAQ status

- DAQ integration of outer detectors is in progress.

+ Detectors integrated in structure:


- * ECL (barrel) - Completed and stably running with the global Belle II DAQ.
- * KLM (barrel) - Being tested with Pocket DAQ. Firmware debugging in progress.
- * TOP - All installed modules are being tested using Pocket DAQ(stand-alone DAQ), module by module basis. Integration in Belle II DAQ is in progress.
 - + Cosmic ray data taking with Pocket DAQ is going on for all installed modules
 - + Feature extraction firmware (TOP) is still under debugging.

+ CDC test stand:

- * A separate Belle II DAQ is prepared.
- * The cosmic ray data taking with 60 FEE modules is stably running.
- * One TOP module is installed near the CDC for the test in the cosmic ray with a tracking information.
- * The data stream from TOP is combined with the CDC data stream and the data taking is started.
 - > The ending date of data taking was elonged to Sep(?).

Live CDC event display

- Full readout chain confirmed to work:
FEE->COPPER->Readout PC-> HLT processing (Unpacker)
-> Storage(sampling) -> Express Reco -> **evdisp**



- VXD integration was tested in DESY test beam

- + The DESY test beam DAQ was fully operational and worked stably up to 2 kHz in beam.
- + The Run Control was fully implemented with both SVD and PXD readouts.
- + “Event mixing” was observed inside both of SVD readout (FTB) and DHE/DHC/ONSEN in PXD readout, although the event mis-match at event builder 2 was not occurred.

- * Event numbers are properly distributed to detectors from FTSW which are embedded in the raw data header of each detector data.


- * Event numbers embedded in the raw data body in PXD/SVD were mis-matched.

-> Investigation by both PXD and SVD FEE experts is being done.


- + The Rol feedback from HLT to ONSSEN was confirmed to work.

- * Because of channel mismatch between DHP and DHE, the remapping had to be implemented, which could not be completed during beam test.




-> Had to use large-size Rols.



Hit Map Ladder 1.1.2



Hit Map Ladder 2.1.2




2 PXD sensors

track reconstructed by HLT

Rols obtained from tracks


DAQ for DESY beam test



Goals of this workshop (for DAQ)

- Discussion on the status and problem in the further detector integration
 - * TOP <- On-going top-priority issue.
 - * KLM <- When can we integrate in global DAQ? Urgent issue.
 - * ARICH
 - * Endcap ECL
- Prospects for GCRT (Global Cosmic-Ray Test)
 - * Trigger for GCRT
 - * Schedule : What detectors in DAQ?, Detector Roll-in schedule.
- Preparation for Phase II run
 - * Test of VXD readout at DESY-TB
 - * Issues in DAQ preparation for Phase II run.
 - * DAQ configuration for Phase II

Partitioned DAQ operation during Phase II run



Cosmic trigger
locally generated

* All DAQ equipments are placed in E-hut/server room and operated in "partitioned DAQ" framework.
* Need to lay fibers from B1 to E-hut.